

ADDENDUM NO. 5

(4/25/2018)

This addendum #5 to the “Ipswich River Substation – Site Construction” bid documents released on 3/29/18 contains responses to several questions that have come up during the bid process:

- There are foundation interferences with the proposed firewall at Waters River that will require more extensive review. The foundation and installation of this firewall are being removed from this scope.
- Contractor shall furnish a DuraBarrier firewall, 19’ long and 18’ high, designed for fire on both sides of wall. Furnish all above grade materials, including wall system, posts, and fire resistant covering material for posts and anchor bolts. Wall materials shall be delivered to the site and stored crated in a location within the substation designated by PMLP. Furnish a complete set of design foundation reactions and installation instructions provided by the vendor.
- Helical piles supporting the 23 kV steel poles along the bike path are specified as provided by Hubbell Power Systems.