

ADDENDUM NO. 1

(3/7/2018)

The purpose of this addendum is to clarify several follow up questions that surfaced after the release of the “Ipswich River – Substation Equipment Package” bid documents, released on 2/23/18.

1. All grounding conductors and grounding connections will be provided by others. Packager needs to provide attachment provisions on structures.
2. Foundation design will be done by others based on information provided by the packager. Foundations for the circuit breakers will be a concrete block approx.. 5 feet deep. We have commonly seen 1” x 24” anchor bolts provided for these breakers, but this will need to be verified by the packager.
3. Other equipment not listed in this RFP (hardware, insulators, etc.) will be provided by others in a future construction bid.
4. 115kV tap wire is to be provided in this bid as per the drawings and bill of materials.
5. Switch ground mats are not required in this procurement.